

**LESOTHO LOWLAND WATER SUPPLY SCHEME FEASIBILITY  
STUDY**

**WATER RESOURCES ASSESSMENT OF FINAL DEVELOPMENT  
OPTIONS**

May 2004

Prepared by :

WRP Consulting Engineers (Pvt) Ltd.  
PO Box 564  
Hilton  
PIETERMARITZBURG  
3245

For :

The Project Manager  
Lesotho Lowlands Water Supply Scheme Feasibility Study  
Parkman Ltd.  
3 Orpen Road  
MASERU WEST  
105

This report is to be referred in bibliographies as :

Lesotho Lowlands Water Supply Scheme Feasibility Study (2004). Water resources assessment of final development options. Prepared by WRP Consulting Engineers.

The report was prepared by :

W. Schäfer (WRP Consulting Engineers) - Technical content, editing and review

C. Seago (WRP Consulting Engineers) - Technical content

## TABLE OF CONTENTS

<b>1. INTRODUCTION</b>	
1.1. BACKGROUND TO THE STUDY	2.1
1.2. APPROACH TO THE STUDY	2.1
1.3. LAYOUT OF THE REPORT	2.2
<b>2. RAINFALL</b>	
2.1. OVERVIEW	2.1
2.2. PRELIMINARY SCREENING	2.1
2.3. PATCHING	2.2
2.4. FINAL SELECTION OF RAINFALL GAUGES	2.2
<b>3. STREAMFLOW</b>	
3.1. OVERVIEW	3.1
3.2. SCREENING AND EVALUATION	3.1
3.3. PRELIMINARY CALIBRATION AND PATCHING OF RECORDS	3.3
3.4. STREAMFLOW CALIBRATION	3.3
3.5. STREAMFLOW SIMULATION	3.5
3.6. STOCHASTIC STREAMFLOWS	3.8
<b>4. ANALYSIS PROCEDURE</b>	
4.1. OVERVIEW OF THE MODEL	4.1
4.2. DESCRIPTION OF PENALTY TYPES	4.2

---

<b>5. WATER RESOURCES ANALYSES</b>	
5.1. OVERVIEW	5.1
5.2. HOLOLO/NGOAJANE SYSTEM	5.3
5.3. HLOTSE SYSTEM	5.6
5.4. MAKHALENG SYSTEM	5.8
<b>6. REFERENCES</b>	<b>6.1</b>